

Contract : Highways Maintenance 2005-2010 (CONWAY)

Request Ref. : ME7152/18378

Description : b.taylor

Dated : 26/08/2009 16:52:42

Items Suspended : 27/08/2009 09:08:41

Follow Up Date : 27/08/2009 00:00:00

Order Number : 14578 Byron Avenue - Planed footway reconstruction works - May - Jul 09

Job Number : 90434863 Footways - planned works - Please provide estimate for planned footway reconstruction works (Enquiry 12199785)

Location : entire length

Street : Byron Avenue, New Malden, Surrey

Area : New Malden, Surrey

Feature No. : 9,999.00

Feature Id :

Action Officer : F M CONWAY

Ordered Price Factor : Routine Maintenance & Supplies

Remaining Value : -4,689.23

Requested Price Factor : Routine Maintenance & Supplies

Requested Value : 46,115.53

Remeasured Price Factor :

Amount to Pay: ~~45974.23~~ 45954.80

Item No.	SOR Item	Description	Remaining Quantity	Req. Quantity	Remeasured Quantity
10	H02181D	Take up or down and set aside for reuse granite kerbs	760.00	381.90	✓
20	H11411D	Remove from store and relay Granite kerb Type G1 curved not exceeding 12m radius	760.00	381.90	✓
30	H02194D	Take up or down and remove to tip off Site precast concrete kerbs	200.00	629.30	585.06
40	H11160D	Granite kerb Type G1 laid straight or curved exceeding 12m radius	200.00	585.06	✓
50	H02210C	Take up or down and set aside for reuse precast concrete slab paving 50mm thick	1,040.00	50.85	✓
60	H11630C	Remove from store and relay 50mm thick precast concrete slabs in footway with fine aggregate to BS 882 Grading C bedding	1,040.00	50.85	✓
70	H02224	Take up or down and remove to tip off Site precast concrete slab paving 50mm thick	260.00	.00	—
80	H11620D	50mm thick precast concrete slabs in footway with mortar bedding	260.00	595.52	✓
90	H06102D	Excavation of unacceptable material Class U1 in cutting or other excavation	240.00	371.80	✓
100	H06110D	Extra over excavation for excavation in Hard Material in cutting or other excavation	240.00	371.80	✓
110	H06141D	Disposal of unacceptable material Class U1	240.00	371.80	✓
120	H06220D	Completion of formation on material other than Class 1C, 6B or rock in cuttings	2,070.00	2,351.83	✓
130	H11602D	100mm thick wet lean concrete 1 sub-base	2,070.00	1,705.46	✓
140	H11661D	Footway comprising dense macadam binder course 50mm thick and close graded macadam surface course 25mm thick	770.00	1,705.46	✓
150	H05381C	Raise the level of size exceeding 0.1m2 but not exceeding 0.5m2 service cover and frame on any size brick 150mm or less	60.00	121.00	✓
160	H05382C	Raise the level of size exceeding 0.5m2 service cover and frame on any size brick 150mm or less	30.00	51.00	✓
170	H01100	Establish and subsequently remove Traffic Management Layout 1, basic length of 300m	1.00	1.00	✓
180	H01102	Maintain Traffic Management Layout 1, basic length of 300m	30.00	15.00	✓
190	99999999	interim	.00	-70,000.00	✓
200	99999999	interim	.00	-30,000.00	✓
210	H11320B	Precast concrete edging Type EF1 laid straight or curved exceeding 12m radius	.00	25.00	✓
220	H11600D	100mm thick Type 1 unbound sub-base	.00	2,028.05	✓
230	H07210C	Tack coat	.00	1,705.46	✓

27/08/2009

Payment Request Remeasurement Sheet

Page 2 of 2

Item No.	SOR Item	Description	Remaining Quantity	Req. Quantity	Remeasured Quantity
240	H05430	Replacement and repair of existing cover and frame on any size brick chamber	.00	3.00	✓
250	H05451	Cleaning existing gully	.00	8.00	✓
260	H05415	Remove from store and reinstall size exceeding 0.5m2 service cover and frame on any size precast concrete chamber	.00	5.00	✓
270	H07318C	Saw-cutting existing pavement saw-cuts exceeding 50mm but not exceeding 70mm in depth	.00	1,011.20	✓
280	H07409D	Patching 100mm thick Reinstatement Classification Type 3 with close graded macadam surface course	.00	252.75	✓
290	99999999	a/r cuts to kerb 6*2	.00	12.00	✓

Comments:

Please close job when payment is made.

Inspection Date : 28/8/09

Inspected By : R. TAYLOR

Signed : 