



Re-align kerb to allow turns into Herten Way

Potential future Bus Stop 1

Remove existing lay-by and construct new footway

New pedestrian plateaux with bus friendly ramps

New 3m Wide Footway - potential future shared use footway / cycleway

Widen existing one way road to 7.3m to create new two way road

Relocated Bus Stop

Future potential Bus Stop 2

New right turn out of Herten Way

New traffic signal controlled junction with pedestrian / cycle crossing facilities

Convert Bus Stop to maintenance bay

- ### NOTES
- Excavate existing verge to allow for new carriageway construction consisting of 250mm thick GSB, 120 thick AC32/BASE, 60mm thick AC20/BIN and 40mm thick AC10/SMA/SURFpsv65
  - Plane existing carriageway surface, apply K170 bond coat and lay 40mm thick AC10/SMA/SURFpsv65
  - Plane existing carriageway surface, apply K170 bond coat and lay 40mm thick AC10/SMA/SURF psv68+
  - Excavate existing verge to allow for new footway/cycleway construction consisting of 150mm thick GSB, 60mm thick AC20/BIN and 20mm thick AC6/CLOSE SURF
  - Excavate existing verge to allow for new footway/cycleway construction consisting of 150mm thick GSB, 60mm thick AC20/BIN and 20mm thick AC6/CLOSE SURF (**Masterint or similar approved, Buff or Red in Colour**)
  - Excavate to allow for new footway construction consisting of 200mm thick GSB, 30mm thick laying course sand and 65mm thick concrete block paving as specified
  - New kerblines
  - New footway edging

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. (100019782) (2011)."

|      |   |        |              |
|------|---|--------|--------------|
| A    | Additional surfacing works at roundabouts - maintenance bay added | PC     | Jan '16      |
|      |   |        |              |
|      |   |        |              |
|      |   |        |              |
|      |   |        |              |
| Rev. | Revision Details  | Rev by | Chk by Date: |

**Doncaster**  
Metropolitan Borough Council

**REGENERATION & ENVIRONMENT DEVELOPMENT**  
*MAJOR PROJECTS AND INVESTMENT*

Civic Offices  
Waterdale  
Doncaster, DN1 3BU  
Assistant Director: Scott Cardwell

Project

**HERTEN WAY SCHEME**

Drawing Title

**GENERAL ARRANGEMENT**

|             |            |                  |                             |
|-------------|------------|------------------|-----------------------------|
| Drawn by    | Paul Carey | e-mail           | xxxx.xxxxx@xxxxxxxxx.xxx.xx |
| Approved by | CR         | Telephone        | 01302 735098                |
| Date        | Dec 2015   | Fax              | 01302 735028                |
| Sheet       | 1 of 1     | Stage / Revision | As Built                    |
| Scales      | 1:500@A1   | Drawing No.      | 29645/GA                    |