

APPENDIX M



YOUNG PERSON'S RISK ASSESSMENT

Date	July 2017	
Version	1.0	
Review	July 2018	
Owner		

PREMISES: Myrtle Park**APPENDIX M: Young persons risk assessment**

HAZARDS	CURRENT CONTROL MEASURES	ADDITIONAL CONTROLS	ACTION BY WHO	ACTION BY WHEN	DONE
Plant and machinery	<ul style="list-style-type: none"> • Appropriate plant handling certificates certification to be provided by contractor • Hire of plant and machinery from approved plant hire companies • Daily checks in accordance with hire contract • Movement on site with hazard warning lights 	<ul style="list-style-type: none"> • Hi Vis Jacket to be worn on site. • Site awareness. No go areas identified and understood by young person • Accompanied by an adult at all times 	Event Manager Site Manager	Arrival on site	
Manual Handling	<ul style="list-style-type: none"> • Manual handling eliminated where possible 	<ul style="list-style-type: none"> • Young person advised not to engage in manual handling of equipment. • Appropriate duties to be given suitable for the young person's ability. 	Event Manager Site Manager	Arrival on site	
Lone Working	<ul style="list-style-type: none"> • Adult staff working as part of team. 	<ul style="list-style-type: none"> • Young person to be accompanied and under the supervision of an adult at all times • Young person informed they should be accompanied by an adult at all times. 	Event Manager Site Manager	Arrival on site	
Slips, trips and falls	<ul style="list-style-type: none"> • Areas of risk to display 'risk of tripping' signs • Removal of debris/arising from working and public areas • Daily site inspections • Supply of river sand/bark chippings for very wet areas 	<ul style="list-style-type: none"> • Appropriate footwear to be worn whilst on site • Young person to be made aware of hazards on site 	Event Manager Site Manager	Arrival on site	
Fall from MEWP	<ul style="list-style-type: none"> • Harness and lanyard to be 	<ul style="list-style-type: none"> • Young person advised to keep away 	Event	Arrival on site	

	<ul style="list-style-type: none"> used Basket handrail to be used Operator to remain within basket at all times Cherry picker not to be driven in elevated position 	from mobile elevated lifting platforms.	Manager Site Manager		
Vehicle Movement	<ul style="list-style-type: none"> Maximum speed limit of 5mph to be observed Vehicle access monitored Hazard warning lights to be used Phased delivery schedule Vehicles to reverse with banks man 	<ul style="list-style-type: none"> Hi Vis Jacket to be worn on site. Site awareness. No go areas identified and understood by young person Accompanied by an adult at all times 	Event Manager Site Manager	Arrival on site	
Electric Shock	<ul style="list-style-type: none"> Generators and site electrics installed by approved electrical contractor Generators guarded from public with fencing or barrier 	<ul style="list-style-type: none"> Young person informed not to touch any electrical equipment or generators. 	Event Manager Site Manager	Arrival on site	
Use of tools	<ul style="list-style-type: none"> Employees to be trained on equipment Equipment to be visually checked prior to use Personal protective equipment to be used 	<ul style="list-style-type: none"> Young person to be made aware of tools that cannot be used. Only tools suitable and appropriate to the young persons ability to be used. Young person to be accompanied by an adult at all times. 	Event Manager Site Manager	Arrival on site	
Noise	<ul style="list-style-type: none"> Appropriate hearing protection to be provided 	<ul style="list-style-type: none"> Avoid environments where young person is exposed to loud noise. 	Event Manager Site Manager	Arrival on site	
Weather	<ul style="list-style-type: none"> Appropriate PPE to be worn. 	<ul style="list-style-type: none"> Young person to be made aware of risks i.e. sunburn, hot/cold weather 	Event Manager Site Manager	Arrival on site	
Drowning	<ul style="list-style-type: none"> River fenced off 	<ul style="list-style-type: none"> Young person to be made aware of risks associated with river and told not to breach fencing. 	Event Manager Site Manager	Arrival on site	

