

KIER SERVICES HOUSING MAINTENANCE

Cambridge City Council

HHSRS Works

Schedule of Works

[illegible]

338,550.00

Schedule of Works

65,015.00

СВТ.

ERVICES HOUSING MAINTENANCE

e City Council

orks

of Works

DESCRIPTION	Quant	UOM	Rate	Total
<u>Molwood Close 22-25, 68-71, 72-75, 76-79, 80-83, 84-87, 88-91, 92-95, 96-99, 100-103, 1-4, 5-12, 13-15, 16-19, 52-59, 60-67, 104-107, 108-115, 116-119, 120-123, 124-131, 132-135, 48-51</u>				
Carry out the removal of the existing timber rails to the front of the block and replace with a UPVC screen, allowance made for a vented top panel and 4mm toughen 6.4mm laminate glass to the lower panels. Approx. size 1.900mm x 2.100mm	1	Item	£ 890.00	£890.00
Carry out the removal of the existing timber rails to the front of the block and replace with a UPVC screen, allowance made for a vented top panel and 4mm toughen 6.4mm laminate glass to the lower panels. Approx. size 2.300mm x 2.100mm	23	nr	£ 1,120.00	£25,760.00
To the existing stair handrail leading to the first floor, due to not meeting required standards, supply and fix to the existing timber rails 41mm x 41mm pre finished softwood spindles vertical @ 100mm centres, fixings will be Torx-Fast Multi Purpose security Screw 5.0 x 60mm, spindles to finish to the underside of the existing handrail and to the top of each tread,	23	nr	£ 1,125.00	£25,875.00
				£52,525.00

1. Check if all timber allowed for. ✓

2. Time ✓

Diff with Ctw
A P. 2. 20

Schedule of Works

Tom ~~at~~ § 1787-2B.

KIER SERVICES HOUSING MAINTENANCE

Cambridge City Council

HHSRS Works

Schedule of Works

			DESCRIPTION	Quant	UOM	Rate	Total
			<u>Hazelwood Close 29-32, 33-36, 37-40, 117-124, 125-132, 1-4, 5-12, 13-16, 17-24, 25-28,</u>				
			Carry out the removal of the existing timber rails to the front of the block and replace with a UPVC screen, allowance made for a vented top panel and 4mm toughen 6.4mm laminate glass to the lower panels. Approx. size 1.900mm x 2.100mm	10	nr	£ 899.00	£8,990.00
			Carry out the removal of the existing timber rails to the front of the block and replace with a UPVC screen, allowance made for a vented top panel and 4mm toughen 6.4mm laminate glass to the lower panels. Approx. size 2.300mm x 2.100mm	10	nr	£ 1,120.00	£11,200.00
			To the existing stair handrail leading to the first floor, due to not meeting required standards, supply and fix to the existing timber rails 41mm x 41mm pre finished softwood spindles vertical @ 100mm centres, fixings will be Torx-Fast Multi Purpose security Screw 5.0 x 60mm, spindles to finish to the underside of the existing handrail and to the top of each tread,	10	nr	£ 1,085.00	£10,850.00
							£31,040.00

1. ? if all timber allowed. ✓
2. Time ✓. ~~Not~~ Decorated.

Diff mth
CWA 255-30

Total Off \$566.28.
+ Decs Cost. ??

Schedule of Works

Diff with CHW
* 310-98

Schedule of Works

11/11/11

Note: Includes decorative
ext stain/paint.

[illegible]

[illegible]